		PROJECT					
		ADDRESS					
SR #	**DWG NO.**	**CSI NO.**	**DESCRIPTION**	**QUANTITY**	**UNIT**	**UNIT COST**	**TOTAL COST**
		001000	**GENERAL REQUIREMENTS**				
1			SUPERVISION AND COORDINATION	1	LS		
2			SUBMITTALS AND SHOP DRAWINGS	1	LS		
3			FINAL CLEANING	1	LS		
4			MOBILIZATION COSTS	1	LS		
5			BOND @ 2%	1	LS		
6			TEMPORARY CONTROL & FACILITIES	1	LS		
7			SPECIAL NOTES: - PROTECT AND COVER EXISTING FURNITURE AND OTHER ITEMS		-		
						SUBTOTAL	**$0.00**
		100000	**DIVISION 10 – SPECIALITIES**				
			TOILET ACCESSORIES				
8	A4.1		BCS: BABY CHANGING STATION	2	EA		
9	A4.1		GB-1: 18" GRAB BARS	2	EA		
10	A4.1		GB-1: 36" GRAB BARS	6	EA		
11	A4.1		GB-1: 42" GRAB BARS	6	EA		
12	A4.1		MG-2: 2'-0"W X 3'-0"H MIRROR GLASS	4	EA		
13	A4.1		MG-2: 5'-0"W X 4'-0"H MIRROR GLASS	2	EA		
14	A4.1		MG-2: 7'-6"W X 4'-0"H MIRROR GLASS	2	EA		
15	A4.1		MH: MOP HOLDER	2	EA		
16	A4.1		ND: NAPKIN DISPOSAL	13	EA		
17	A4.1		PTD-1: PAPER TOWEL DISPENSER	2	EA		
18	A4.1		PTD-2: PAPER TOWEL DISPENSER	1	EA		
19	A4.1		SD: SOAP DISPENSER	12	EA		
20	A4.1		TTD: TOILET TISSUE DISPENSER	17	EA		
			TOILET PARTITIONS				
21	A4.1		TOILET PARTITIONS W/ ASSOCIATED DOOR AT 5'-0"HT MANUFACTURER: SCRANTON STYLE: HINY HIDERS, HPDE COLOR: STAINLESS TEXTURE: HAMMERED	93	LF		
22	A4.1		URINAL PARTITION AT 3'-6"HT MANUFACTURER: SCRANTON STYLE: HINY HIDERS, HPDE COLOR: STAINLESS TEXTURE: HAMMERED	6	LF		
			CORNER GUARDS				
23	A1.1		CG: CORNER GUARDS	200	LF		
			KEY STORAGE				
24	A1.1		A07: KEY STORAGE	1	EA		
			FIRE EXTINGUISHER/ CABINETS				
25	A1.1		FE-1: FIRE EXTINGUISHERS	2	EA		
26	A1.1		FEC-1: FIRE EXTINGUISHER CABINETS	7	EA		
			SIGNAGES				
27	A4.5		RELOCATE EXISTING SIGN W/ (2) SIGN POSTS AT BOOKSTORE	1	EA		
28	A4.5		TYPE-A: RESTROOM IDENTIFICATION SIGNAGE ROOM NUMBER: SOLID PLAQUE TOP PANEL WITH PERMANENT 1-1/2" RAISED VERBAIGE - BRAILLE ROOM NAME: SOLID PLAQUE BOTTOM PANEL WITH PERMANENT 1" RAISED VERBAIGE - BRAILLE SYMBOL: 6"H SIZE: 7-1/2" BOTTOM WIDTH X 10-3/4" TOP WIDTH X 1'-2"H	5	EA		

		PROJECT				
		ADDRESS				

SR #	DWG NO.	CSI NO.	DESCRIPTION	QUANTITY	UNIT	UNIT COST	TOTAL COST
29	A4.5		TYPE-B: ROOM IDENTIFICATION SIGNAGE ROOM NUMBER: SOLID PLAQUE TOP PANEL WITH PERMANENT 1-1/2" RAISED VERBAIGE - BRAILLE ROOM NAME: NAME/ TITLE PRINTED PAPER INSERT SIZE: 9" BOTTOM WIDTH X 10-3/4" TOP WIDTH X 0'-8-1/2"H	5	EA		
30	A4.5		TYPE-C: ROOM IDENTIFICATION SIGNAGE ROOM NUMBER: SOLID PLAQUE TOP PANEL WITH PERMANENT 1-1/2" RAISED VERBAIGE - BRAILLE ROOM NAME: NAME/ TITLE SOLID PLAQUE TOP PANEL WITH PERMANENT 3/4" RAISED VERBAIGE ROOM NAME: NAME/ TITLE PRINTED PAPER INSERT SIZE: 9-1/4" BOTTOM WIDTH X 10-3/4" TOP WIDTH X 0'-7-1/2"H	18	EA		
31	A4.5		TYPE-D: EXIT SIGNAGE TEXT: SOLID PLAQUE TOP PANEL WITH PERMANENT 1-1/2" RAISED VERBAIGE - BRAILLE SIZE: 9" WIDTH X 3" H	4	EA		
						SUBTOTAL	**$0.00**

TOTAL BASE BID (Div 10)	**$ -**

GENERAL NOTES

1. Takeoff prepared as per provided scale on plan.
2. Where scale is NTS, Manual scaling is done to give approximate quantity.
3. It is highly recommended to have a field view prior to bid.

UNITS ABBREVIATION

LF	LINEAR FOOT	SF	SQUARE FOOT
EA	EACH	CY	CUBIC YARD
LOC	LOCATION	LS	LUMP SUM